



Ntshovelo Mining Resources (Pty) Ltd  
Vlakvarkfontein Colliery  
(Registration No. 2005/014878/07)

Ntshovelo Mining Resources (Pty) Ltd  
Vlakvarkfontein Colliery  
Portion 13 of the farm  
Vlakvarkfontein 213R  
Kendal  
2225

16 July 2020

To: FlowCentric Mining Technology

**RE: Water Evaporation System**

This letter serves to confirm that FlowCentric Mining Technologies manufacture, installed and maintained 3 x 75kW mechanical evaporators (complete with MCC, cabling and pumps) powered by a 650kVA diesel generator, due to inability to source sufficient capacity from the nearby Eskom grid.

The system was specified and designed to evaporate 2.8 ML/day against water inlet recharge of 2.5 ML/day. Evaporators managed to sustain water level within safe limits at our water storage dams for a period of 11 months against 12 months planned. About 60% of 830 ML was evaporated from 23 July 2019 to 05 July 2020 to enable mining activities to commence without any delays.

Yours Faithfully

Engineering Manager  
Duncan Mjadu