

# GLENCORE

Date: 7 July 2022

## **REFERENCE LETTER FOR COMPLETED EVAPORATOR PROJECT**

To Whom It May Concern

This letter serves as confirmation that *FlowCentric Mining Technology* has successfully completed the installation of 2 x evaporator systems at Zonnebloem Colliery. The scope required a system that can evaporate up to 1 Ml/day.

The units can be controlled remotely via the *Remote Operator* application or from the MCC on site.

The project included the design, installation, and commissioning of the following equipment:

- 2 x 45 kW Rhino evaporation fans
- 2 x 90 m<sup>3</sup>/hr KSB pumps
- Suction pipes, pipe floats, foot valves
- 1 x containerised MCC with all associated electrical panels, electrical protection, associated control instrumentation, field isolator panels, flow sensors, wind and rain sensor.
- Stainless steel handrails

Completion was issued on 22 June 2022. The evaporator units are running 12 hours a day based on an auto start and stop of 06:00 to 18:00.

The project is required to aid in the evaporation of water from the Pollution Control Dam to prevent decant into the environment.

Yours faithfully

*Wayne Crouch* Crouch, Wayne  
Jul 7 2022 11:58 am  
DocuSign

GLENCORE OPERATIONS SOUTH AFRICA (PROPRIETARY) LIMITED

Per: Wayne Crouch: Manager, Financial and Project Controls